

PROPERTY ADDRESS

UNIT #

UNIT TYPE

QUOTE REQUESTED FROMDATE

BUDGET TARGET

1 BR

2 BR

3 BR

DEADLINE

Instructions for Contractor: Mark each "Include" box with a ✓ (check) = **YES, quote this item** or an X (X) = **NO, do not quote this item**. Do not leave boxes blank — every line must be marked one way or the other. Fill in the **Qty** column wherever a quantity applies (e.g. number of pot lights, linear feet of baseboard, sq ft of flooring). Use the "Approved Equivalent" column if a specified product is unavailable — substitutions require Daniko approval before ordering. Unit type above determines scope (e.g. number of bedrooms/closets).

KITCHEN

INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
☐			Cabinet Doors	White Shaker — ThermoFoil MDF Smooth white finish • Manufactured in-house • Soft-close hinges • Slow-close drawer slides • Height-adjustable legs • 5/8" melamine box	
☐			Cabinet Hardware	Bar Pull — Brushed Nickel, 5"L Horizontal on all drawers (centred) • Cabinet knob: 40mm x 22mm brushed nickel, vertical on all doors	
☐			Cabinet-to-Ceiling Gap	Crown Molding — If Applicable Where a gap exists between the top of the upper cabinets and the ceiling, install large or stacked crown molding to bridge the space. Applies to small-to-medium gaps only — flag to Daniko if the gap is large enough to require a different solution (e.g. soffit or filler panel). Confirm on-site during walkthrough.	
☐			Countertop	Classic Calacatta 2038 — Quartz 2cm thickness • Double front edge profile • Supplier: Rapid Quartz • Next-day install available	
☐			Backsplash	Olympia Ceramic Subway — Arctic White, Beveled High Gloss 3" x 6" • 70/30 Brick Lay/Subway install • 15 sq ft / 136 pcs per box	
☐			Grout	Flextile Unsanded Grout — Snow White 551 25 lb bag	
☐			Kitchen Faucet	MOEN Adler Pull-Down — Spot Resist Stainless Steel Model 87233SRS • Power Clean spray technology • Reflex smooth-docking pulldown • Single handle, deckplate included • Sizing/reach to be field-verified against sink layout	
☐			Kitchen Sink	Stylish S-411T Undermount Single Bowl — Stainless Steel 16-gauge stainless steel • Single large basin • Model S-411T • Replaces previous double-basin standard	
☐			Island Countertop Overhang	15" Overhang — If Applicable Units with a kitchen island only • 15" overhang on seating side for a 36"H island, sized for standard bar stool clearance • Countertop material and colour to match main kitchen countertop spec • Confirm island exists on-site before quoting	
Electrical — Kitchen					
☐			GFI Receptacle	GFCI Outlet — White, 20A 20A 125V tamper-resistant self-test GFCI • Install adjacent to sink • Required by Ontario Electrical Code	
☐			Fridge Dedicated Circuit	Confirm Circuit — If Refrigerator Being Relocated Confirm refrigerator is on its own dedicated circuit back to the panel, or that the existing circuit is ESA-compliant for the relocated position. Flag to Daniko if the circuit is shared with other kitchen loads — do not proceed without confirming, to avoid overloading.	
☐			Hydro Panel	Full Panel Replacement — Kitchen Confirm whether the existing in-suite panel is breaker-style. If not already	

☐			Replacement	breaker-style (e.g. older fuse-style panel), replace with a breaker-style panel. Contractor to confirm amperage and breaker count on-site and note below.	
✂ Electrical Permit Notice: Any electrical work (receptacles, switches, fixtures, fans, panels) must comply with the Ontario Electrical Safety Code. Where a permit is mandated, the contractor is responsible for obtaining it — the cost of the permit is assumed to be included in the quoted price and will not be treated as an extra unless flagged and approved by Daniko in writing before work begins.					
●BATHROOM					
INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
☐	_____		Vanity Cabinet	White Shaker — Match Kitchen Manufactured in-house • Same finish and hardware as kitchen	_____
☐	_____		Vanity Top	Classic Calacatta 2038 — Match Kitchen 2cm • Double front edge • Rapid Quartz	_____
☐	_____		Vanity Sink	Rectangular Undermount — White 16"W x 20"L • Supplier: Rapid Quartz	_____
☐	_____		Vanity Faucet	MOEN Findlay Single Hole — Chrome Model 84516 • Single handle • Push-down drain assembly included • Deckplate included for 1 or 3-hole install	_____
☐	_____		Tub & Shower Set	MOEN Adler — Chrome Model L82839 • Single handle round wall mount • 1-spray bathtub shower faucet with rain shower head • Posi-Temp pressure-balancing valve • Confirm existing brass shower valve is fully replaced, not just the trim • Trim to be caulked at wall on completion	_____
☐	_____		Bathtub	American Standard — Porcelain Enamelled Steel 30"W x 60"L • White • Left or right handed	_____
☐	_____		Tub Surround Tile	Ceramic Subway — Arctic White, Bright 4"W x 16"L • 70/30 Brick Lay/Subway • Grout: Snow White Unsanded 551	_____
☐	_____		Wall Waterproofing (Tub/Shower)	Schluter KERDI-BOARD System Applies throughout the full wet-wall assembly — tub surround backing, tile substrate, and base/bottom plate. Replaces cement board. See Schedule A for the window waterproofing detail within tub/shower surrounds.	_____
☐	_____		Toilet	American Standard — 2-Piece Elongated White • Standard flush	_____
☐	_____		Shower Rod	Zenna Home Curved Hotel Rod — Chrome Model 99336 • Rust-resistant painted steel and zinc construction • Curved design • Fixed wall mount, screwed (not tension) • Adjustable 56"-72" • Install 60" above tub	_____
☐	_____		Bath Accessory Kit	MOEN Preston — Chrome, 3-Piece Towel ring, toilet paper holder, towel bar	_____
☐	_____		Bathroom Fan	Cyclone HushTone ESLPD3S100H — Ultra-Quiet Ceiling Exhaust White • Continental Fan Mfg • Replaces Air King AS50 as new Daniko standard • CFM/sones rating to confirm on cut sheet	_____
☐	_____		Mirror	Rectangular Wall Mirror — 20" x 28" Standard trim, white	_____
Electrical — Bathroom					
☐	_____		GFI Receptacle	GFCI Outlet — White, 15A 15A 125V tamper-resistant self-test GFCI • Required by Ontario Electrical Code near water	_____
✂ Electrical Permit Notice: Any electrical work (receptacles, switches, fixtures, fans, panels) must comply with the Ontario Electrical Safety Code. Where a permit is mandated, the contractor is responsible for obtaining it — the cost of the permit is assumed to be included in the quoted price and will not be treated as an extra unless flagged and approved by Daniko in writing before work begins.					
●FLOORING					

INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
☐			Luxury Vinyl Plank	SPC Rigid Core LVP — All Living Areas incl. Kitchen & Bathroom 5mm • 9" wide • 48" length • 1.5mm premium padding • Colour: warm oak / natural tone • Loose lay, glued down, or perimeter glue	
☐			LVP Adhesive	Ultrabond ECO 360 Premium Adhesive 4 GL • Used where glue-down install specified	
●PAINT					
INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
☐			Walls	DULUX Ultra Interior — Eggshell, White 18.3L • Colour: Chantilly Lace OC-65 (Sherwin Williams equivalent) • All living areas, bedrooms, kitchen, hallways	
☐			Ceilings	DULUX Ultra Interior — Flat, White 18.3L • All ceilings	
☐			Trim & Doors	DULUX Ultra Interior — Semi-Gloss, White 18.3L • All baseboards, casings, and interior doors	
☐			Bathroom Walls & Ceiling	Zinsser Perma-White Mould & Mildew-Proof — Tintable Satin 3.78L • Self-priming, washable/scrubbable • Mould and mildew resistant, 5-year film guarantee • Replaces standard wall/ceiling paint in bathroom only • If applied near shower, wait 24 hrs before use	
☐			Primer	Glidden Ultra Interior — White 18.9L • Interior drywall and plaster • Apply before top coat on bare surfaces	
●DOORS, TRIM & HARDWARE					
INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
☐			Interior Door	2-Panel Logan Slab — Primed Hollow Core White semi-gloss • 30"W x 80"H standard	
☐			Privacy Lever	Weiser Kim — Satin Nickel, with Lock Bedroom and bathroom doors	
☐			Passage Lever	Weiser Kim — Satin Nickel, No Lock Hallway and closet doors	
☐			Dummy Lever	Weiser Kim — Satin Nickel, Dummy Closet doors (non-latching)	
☐			Door Hinges	Round — Satin Nickel 3" with 5/8" radius • Set of 2 per door	
☐			Door Stopper	Brushed Nickel 3 5/32"L x 25/32"W	
☐			Magnetic Catch	Stainless Steel — with Striker Plate Closets and double doors	
☐			Baseboard Trim	Step Bevel — Finger Joint Poplar LVL Primed 1/2" x 5-1/2" x 10' • Paint semi-gloss white to match doors	
☐			Door Casing	Step Bevel — Finger Joint Poplar LVL Primed 3/4" x 3" x 8'	
			Trim Sealant	DAP Alex Flex — Premium Molding & Trim Sealant	



</

✂ **Electrical Permit Notice:** Any electrical work (receptacles, switches, fixtures, fans, panels) must comply with the Ontario Electrical Safety Code. Where a permit is mandated, the contractor is responsible for obtaining it — **the cost of the permit is assumed to be included in the quoted price** and will not be treated as an extra unless flagged and approved by Daniko in writing before work begins.

●CLOSET						
INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT	
☐			Closet Shelves	White Melamine — 5/8" x 16"D 60" and 96" lengths • One set per closet		
☐			Shelf Support	MDF Strip — Shelf Ledger Primed • Per closet		
☐			Closet Rod	Steel Oval — Chrome, 1" x 8' Cut to fit per closet width		
☐			Closet Rod Clips	Chrome — Set of 2 Per rod		
Additional Scope — Front Entry Closet						

🔒 DANIKO SUPPLIES — DO NOT INCLUDE IN QUOTE

Appliances
Fridge • Stove/Range • OTR Microwave
Daniko sources and delivers. Contractor to confirm rough-in dimensions and hook up. **Confirm OTR microwave exhaust is connected to the existing exhaust duct — this replaces any existing standalone ceiling-mounted exhaust fan near the stove, which is to be removed.** Flag to Daniko if no existing exhaust duct is present to connect into.

Entry Lock Set
Deadbolt + handle for unit entry door
Daniko supplies keyed lock. Contractor installs.

Note: Confirm Rough-Ins
Confirm appliance cutout sizes and electrical rough-ins with Daniko before ordering cabinets or countertops.

•WINDOWS & EXTERIOR DOORS

INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
Windows — All Units					
☐			Window Pane Condition	☐All panes intact — no action ☐Missing / cracked pane — replace Flag any broken seals, fogging, or cracked panes during walkthrough	
☐			Window Screening	☐Yes — Replace / Install ☐No — Existing satisfactory Inspect all screens — replace torn, bent, or missing screens. Standard grey fibreglass mesh.	
☐			Window Operation	☐Operational — opens, closes, locks correctly ☐Repair required — specify in notes below All windows must open, close, and latch properly before handover	
Exterior Door to Balcony					
☐			Locking Mechanism	☐Yes — Replace / Install ☐No — Existing satisfactory Test latch, deadbolt, and handle — replace if loose, stiff, or not engaging properly	
☐			Door Screening	☐Yes — Replace / Install ☐No — Existing satisfactory Inspect screen door if present — repair or replace torn/bent screen or damaged frame	
☐			Balcony Door Operation	☐Operational — opens, closes, locks correctly ☐Repair required — specify in notes below	
Interior Doors — General					
☐			Interior Door Slab	Alex Direct 30"x80" Primed Hollow Core — 1-Panel Beveled Shaker Style Model HW26681PFBSHF8 • Smooth, primed, ready for paint • Hollow core, no bore • Replace if applicable — confirm door width per opening on-site, not all doors are 30"	
☐			Door Stops	☐Yes — Replace / Install ☐No — Existing satisfactory Install or replace door stops on all interior doors — Brushed Nickel, spring-style	
☐			Closet / Sliding Door Tracks	☐Track clean and operational — no action ☐Repair / replace track required Test all sliding and bi-fold doors — must operate smoothly with no jumping or binding	
Front Entry Door					
☐			Hinge & Closing Function	Confirm & Repair — If Applicable Confirm top hinge and closing mechanism function properly — door closes fully and latches without sticking or dragging. Adjust or repair as needed. Flag during walkthrough.	

•BLINDS

INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
Contractor to Supply & Install					
☐			Bedroom Windows	Home Decorators Collection 2.5" Faux Wood Blind — White Model 25FWT2448W • Cordless room-darkening, wand tilt • 3" matching valance with returns • Inside mount • Contractor to cut to fit • Contractor supplies and installs	
☐			Living Room Window	Home Decorators Collection 2.5" Faux Wood Blind — White Model 25FWT2448W • Cordless room-darkening, wand tilt • 3" matching valance with returns • Inside mount • Contractor to cut to fit	
☐			Balcony Sliding Door	Vertical Blinds — White, PVC Track-mounted vertical blinds sized to full slider width • Must clear door track and allow full slide operation	
⚠️ Note: Blinds are contractor-supplied and contractor-installed under this scope — not a Daniko-supplied item. Confirm exact window and door measurements on-site before ordering.					
•BEDROOM 1					
INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
Ceiling					
☐			Ceiling	☐ Existing — satisfactory, no action ☐ Repaint — DULUX Ultra Flat White	
Flooring					
☐			Flooring	☐ Yes — Replace / Install ☐ No — Existing satisfactory SPC Rigid Core LVP — 5mm, 9" wide, warm oak tone. Replace if damaged, worn, or mismatched.	
Paint					
☐			Walls	☐ Yes — Replace / Install ☐ No — Existing satisfactory DULUX Ultra Interior Eggshell — Chantilly Lace OC-65. Full room if painting.	
Trim					
☐			Baseboard	☐ Yes — Replace / Install ☐ No — Existing satisfactory Step Bevel Finger Joint Poplar — 1/2" x 5-1/2", semi-gloss white	
☐			Door Casing	☐ Yes — Replace / Install ☐ No — Existing satisfactory Step Bevel Finger Joint Poplar — 3/4" x 3", semi-gloss white	
Main Bedroom Door					
☐			Door	☐ Existing — satisfactory, no action ☐ Replace — 2-Panel Logan Slab, primed hollow core, 30"x80"	
☐			Door Lever	☐ Yes — Replace / Install ☐ No — Existing satisfactory Weiser Kim Privacy Lever — Satin Nickel, with lock	
☐			Trim / Casing	☐ Yes — Replace / Install ☐ No — Existing satisfactory Replace if damaged or missing	
☐			Hinges	☐ Yes — Replace / Install ☐ No — Existing satisfactory Satin Nickel, 3" round with 5/8" radius — set of 2	
☐			Door Stop	☐ Yes — Replace / Install ☐ No — Existing satisfactory Brushed Nickel spring-style	
Closet					

☐		—	Closet Doors	☐Existing — satisfactory, no action ☐Mirrored sliding doors ☐Panel doors (bi-fold or hinged)	
☐		—	Closet Shelves & Rod	☐Yes — Replace / Install ☐No — Existing satisfactory White melamine shelves 5/8"x16" • Chrome steel oval rod 1"x8" • Chrome rod clips	

Windows

☐		—	Window Pane Condition	☐All panes intact — no action ☐Missing / cracked pane — replace	
☐		—	Window Screening	☐Yes — Replace / Install ☐No — Existing satisfactory Replace torn, bent, or missing screens	
☐		—	Window Operation	☐Operational — no action ☐Repair required — specify in notes	

Lighting & Electrical

☐		—	Ceiling Light	☐Existing — satisfactory, no action ☐Flush mount LED — Chrome, 12"D, 4000K ☐Ceiling fan with light — Hampton Bay 36" White, TS-36-028 MWH, pull string	
☐		—	Light Switch	☐Yes — Replace / Install ☐No — Existing satisfactory Leviton Decora 15A — White. Replace if damaged or discoloured.	
☐		—	Receptacle	☐Yes — Replace / Install ☐No — Existing satisfactory Tamper-resistant 15A White. Replace if damaged.	

✂ **Electrical Permit Notice:** Any electrical work (receptacles, switches, fixtures, fans, panels) must comply with the Ontario Electrical Safety Code. Where a permit is mandated, the contractor is responsible for obtaining it — **the cost of the permit is assumed to be included in the quoted price** and will not be treated as an extra unless flagged and approved by Daniko in writing before work begins.

•BEDROOM 2

INCLUDE	QTY	PHOTO	ITEM	DANIKO STANDARD SPEC	APPROVED EQUIVALENT
Ceiling					
☐		—	Ceiling	☐Existing — satisfactory, no action ☐Repaint — DULUX Ultra Flat White	
Flooring					
☐		—	Flooring	☐Yes — Replace / Install ☐No — Existing satisfactory SPC Rigid Core LVP — 5mm, 9" wide, warm oak tone. Replace if damaged, worn, or mismatched.	
Paint					
☐		—	Walls	☐Yes — Replace / Install ☐No — Existing satisfactory DULUX Ultra Interior Eggshell — Chantilly Lace OC-65. Full room if painting.	
Trim					
☐		—	Baseboard	☐Yes — Replace / Install ☐No — Existing satisfactory Step Bevel Finger Joint Poplar — 1/2" x 5-1/2", semi-gloss white	
☐		—	Door Casing	☐Yes — Replace / Install ☐No — Existing satisfactory Step Bevel Finger Joint Poplar — 3/4" x 3", semi-gloss white	
Main Bedroom Door					
				☐Existing — satisfactory, no action	

☐			Door	☐ Replace — 2-Panel Logan Slab, primed hollow core, 30"x80"	
☐		—	Door Lever	☐ Yes — Replace / Install ☐ No — Existing satisfactory Weiser Kim Privacy Lever — Satin Nickel, with lock	
☐		—	Trim / Casing	☐ Yes — Replace / Install ☐ No — Existing satisfactory Replace if damaged or missing	
☐		—	Hinges	☐ Yes — Replace / Install ☐ No — Existing satisfactory Satin Nickel, 3" round with 5/8" radius — set of 2	
☐		—	Door Stop	☐ Yes — Replace / Install ☐ No — Existing satisfactory Brushed Nickel spring-style	

Closet

☐		—	Closet Doors	☐ Existing — satisfactory, no action ☐ Mirrored sliding doors ☐ Panel doors (bi-fold or hinged)	
☐		—	Closet Shelves & Rod	☐ Yes — Replace / Install ☐ No — Existing satisfactory White melamine shelves 5/8"x16" • Chrome steel oval rod 1"x8" • Chrome rod clips	

Windows

☐		—	Window Pane Condition	☐ All panes intact — no action ☐ Missing / cracked pane — replace	
☐		—	Window Screening	☐ Yes — Replace / Install ☐ No — Existing satisfactory Replace torn, bent, or missing screens	
☐		—	Window Operation	☐ Operational — no action ☐ Repair required — specify in notes	

Lighting & Electrical

☐		—	Ceiling Light	☐ Existing — satisfactory, no action ☐ Flush mount LED — Chrome, 12"D, 4000K ☐ Ceiling fan with light — Hampton Bay 36" White, TS-36-028 MWH, pull string	
☐		—	Light Switch	☐ Yes — Replace / Install ☐ No — Existing satisfactory Leviton Decora 15A — White. Replace if damaged or discoloured.	
☐		—	Receptacle	☐ Yes — Replace / Install ☐ No — Existing satisfactory Tamper-resistant 15A White. Replace if damaged.	

✂ **Electrical Permit Notice:** Any electrical work (receptacles, switches, fixtures, fans, panels) must comply with the Ontario Electrical Safety Code. Where a permit is mandated, the contractor is responsible for obtaining it — **the cost of the permit is assumed to be included in the quoted price** and will not be treated as an extra unless flagged and approved by Daniko in writing before work begins.

•CONTRACTOR NOTES & SCOPE CLARIFICATIONS	
ITEM	NOTES / CLARIFICATIONS
Start Date	Confirmed Start Date: Contractor must not begin work before this date. Any earlier access requires written approval from Daniko.
Finish Date	Confirmed Completion Date: Unit must be fully rent-ready by this date. This deadline is firm. Delays that push the move-in date will be subject to a daily holdback. Contractor to flag any risks to this date immediately.
Total Quoted Cost	MATERIALS \$ LABOUR \$ HST \$ TOTAL \$ Quote must itemize labour and materials separately per section. Lump sum quotes will not be accepted.
Payment Schedule	

20%

Deposit — Upon Signing

Due before any work begins. Required to confirm the booking and secure the start date.

Amount: \$ _____

60%

Progress — Major Items Complete

Released once all major scope items are finished and approved. Contractor must submit photos for Daniko sign-off before payment is issued.

Amount: \$ _____

20%

Final — After Deficiency Walk

Released after the final walk-through with Daniko. All deficiencies must be corrected before final payment is issued.

Amount: \$ _____

⚠ Progress payment photo submission is mandatory. Payment will not be released without Daniko approval of submitted photos.

Jobsite Cleanliness

The unit must be left in move-in ready condition upon completion. This is a hard requirement, not a suggestion.

Throughout the Job

- All debris, packaging, and off-cuts removed daily
- Tools and materials stored neatly — no blocking exits
- Dust contained to work area where possible
- No food, drink, or garbage left on site overnight

Upon Completion

- All surfaces wiped down — counters, cabinets, fixtures
- Floors vacuumed and mopped throughout
- Windows, sills, and mirrors cleaned
- Appliances cleaned inside and out
- All trade waste and leftover materials removed
- Unit ready for a tenant to move in — no exceptions

⚠ If the unit is not left in acceptable condition, Daniko reserves the right to deduct professional cleaning costs from the final payment.

Warranty

2-Year Parts & Labour Warranty

By accepting this contract, the contractor agrees to provide a full two-year warranty covering both parts and labour on all work completed under this scope. Any defects in workmanship or materials that appear within 24 months of the confirmed completion date will be repaired or replaced by the contractor at no cost to Daniko Management Ltd.

This warranty does not cover damage caused by tenant misuse, normal wear and tear, or modifications made by a third party after handover.

Contractor Signature

Date

Substitutions

Any substitution to the Daniko Standard Spec must be approved in writing before ordering. Use the "Approved Equivalent" column and flag to Daniko project lead.

Quote Format

Quote must separate labour and material costs per section. Lump sum quotes will not be accepted.

Site Conditions

Contractor responsible for pre-walkthrough. Any scope additions due to unforeseen conditions must be flagged and approved before work proceeds.

Wall Removal (If Applicable)

Note any wall removal/relocation scope for this unit below — location, wall type (load-bearing vs. partition), and any engineering/permit requirements. Leave blank if not applicable to this unit.

Demo & Haul-Away

Removal and disposal of all existing materials being replaced (old cabinets, countertops, flooring, fixtures, doors, trim, etc.) is included in the contractor's scope and quoted price. Site must be left clear of demo debris daily — no accumulation left on-site overnight.

Contractor Notes

● SCHEDULE A — WINDOW WATERPROOFING STANDARD

REQUIREMENT

DETAIL

Scope

Applies to any window located inside a tub or shower surround. This is the mandatory waterproofing method for that condition — not optional, not a "best effort" item.

Frame Build-Out

Build out the window frame using Schluter KERDI-BOARD (see Wall Waterproofing spec, Bathroom section) so that sealant bonds directly to the window's vinyl frame — not to backer board. Backer board is not an acceptable bonding surface at the window perimeter.

Bottom Plate	Bottom plate goes in first and must be pitched toward the shower/tub to shed water away from the frame — no flat or reverse-pitched bottom plates.
Screw Holes	Every screw hole in the frame and build-out must be sealed. No exposed/unsealed fasteners anywhere in the wet zone.
Edge Bonding	Bottom, side, and top edges of the window frame must be fully bonded — full contact seal, no gaps, no partial runs of sealant.
△ Pass/Fail: This detail is inspected at the progress-payment walkthrough. Any window inside a tub/shower surround that does not meet the above (frame build-out, pitched bottom plate, sealed screw holes, fully bonded edges) fails inspection and progress payment will not be released until corrected.	
DANIKO Management Ltd. management@daniko.ca • (289) 212-8196 • daniko.ca DRAFT — Not for distribution Branding to be applied upon approval • v2.0 August 2026	